



**INVITATION TO TENDER PS 01- 10
VALEMOUNT & DISTRICT
VOLUNTEER FIRE HALL
BUILDING ADDITION AND RENOVATIONS
PHASE I – TO LOCK-UP
ADDENDUM NO. 4**

Question:

Please clarify the scope of work to be done to wall finishes and ceiling finishes. The drawings show all finished but Appendix 'A' indicates to lock-up only.

Are the following items in the scope of this tender?

- *Drywall to walls?*
- *Vapour barrier to walls?*
- *R22 batt insulation to walls?*
- *G1S plywood to walls?*
- *Poly to ceiling?*
- *Insulation to ceilings?*
- *Drywall to ceiling?*

Answer:

This tender is to lock-up only as per Appendix 'A' and does not include:

- **Drywall to walls;**
- **Vapour barrier to walls;**
- **R22 batt insulation to walls;**
- **G1S plywood to walls;**
- **Poly to ceiling;**
- **Insulation to ceilings; and**
- **Drywall to ceiling.**

This tender does include:

- **Vapor barrier strip around door and window openings as required by BCBC to provide a proper lap to seal the future vapour barrier.**
- **6" to 4" min sloped polyisocyanurate insulation on 5/8" exterior grade plywood on engineered roof trusses**