



INVITATION TO TENDER PS 02- 09

**SHELL-GLEN VOLUNTEER FIRE/RESCUE HALL – PHASE 1 TO LOCK-UP
BUILDING ADDITION AND RENOVATIONS**

ADDENDUM NO. 2

1. Item number 6 on Addendum No. 1 is to be disregarded. The existing water piping system (as shown in figures 2 and 3) is to be relocated as specified on the drawings.
2. The existing well water line is to be extended as required, to connect to the relocated water piping system. Provide and install all necessary fittings to complete this connection.
3. The “Access Engineering Driveway Specifications” issued in Addendum 1 are generic. Only that part of these specifications that applies to driveway construction should be adhered to for this phase of the project.
4. All new underground lines and pipes are required to be placed on a bed of sand. The backfill must be carefully placed and tamped to a depth of 300mm above the pipes. This backfill shall be free of stones, boulders, cinders and frozen earth.