



Addendum No. 2
Request for Proposal ES-14-04

The Addendum is being issued prior to the closing of the tenders to provide further information, make changes to, or to clarify the Contract Documents and is to be read, interpreted and coordinated with all other parts of the Contract Documents. In the case of a conflict with the balance of the documents, this Addendum shall govern. **Tenders shall acknowledge receipt of this Addendum on the Tender Form and shall attach a signed copy of this Addendum to their Tender.**

This Addendum shall form part of the Contract Documents.

RFP ES-14-04

- Is it permissible for field staff to have access to and conduct field work on the active landfills outside of operating hours?

Response:

For gated, manned sites all work is to be carried out during operating hours. For unmanned sites sampling is only to occur between dawn and dusk. Please refer to section 7.7 WORKSAFE BC.

- Is there any dedicated sampling equipment in any of the monitoring wells from previous sampling events? If so can you indicate which monitoring wells?

Response:

The vast majority of wells are purged by the use of bailers. Only three (3) wells have dedicated sampling equipment (pumps). All three (3) are associated with the Foothills Boulevard Regional Landfill.

- Will the leachate samples be collected from the recirculation system and if so what type of sampling port has been installed?

Response:

The leachate samples are collected from the Foothills Boulevard Regional Landfill leachate re-circulation lift station. Sampling of the leachate is completed by opening the access cover.

Note; During leachate and condensate sampling events a Regional District staff member will be present due to on-site design considerations.

- Has the presence of H₂S been detected during past monitoring rounds?

Response:

Though H₂S has not been detected in past monitoring rounds the Regional District of Fraser-Fort George will not rule out that H₂S could be detected in future monitoring rounds.

- Will the condensate be sampled prior to mixing with the leachate and if so is there a designated sampling port?

Response:

The condensate is sampled prior to mixing with the leachate. There is a dedicated sampling location.

- Are there any confined space hazards associated with leachate or condensate sample collection?

Response:

There are no confined space hazards associated with leachate or condensate sample collection.

Note; During leachate and condensate sampling events a Regional District staff member will be present due to on-site design considerations.

- Are there designated locations for the collection of the surface water samples?

Response:

Please refer to Section 4 PURPOSE, Surface sampling from at least two (2) locations associated with the Foothills Boulevard Regional Landfill site may be undertaken in 2014.

A cost estimate for surface water sampling within the area shown on FIGURE 2 ideally would be included within the RFP should surface water sampling be implemented due to the changes in the regulatory environment.

- Are all the monitoring wells accessible by vehicle?

Response:

The vast majority of wells are accessible by road when accessed with a suitable vehicle.

Date: March 5, 2014

Addendum No. 2 Received.

Signature of Tenderer

Name of Tenderer