



Addendum No. 1

Invitation to Quote ES-21-11

Erosion Remediation Mackenzie Regional Transfer Station

The addendum is being issued prior to the closing of the Invitation to Quote to provide further information, make changes to, or to clarify the Contract Documents and is to be read, interpreted and coordinated with all other parts of the Contract Documents. In the case of a conflict with the balance of the documents, this Addendum shall govern. **Bidders shall attach a signed copy of this addendum to their quote.** This addendum shall form part of the Contract Documents.

Question #1: Do you have required specs for the construction fencing?

Answer #1: Here are specifications for the construction fencing suggested by consultants:

- Size: 6'x9.5' or 182.9cm x 289.6cm
- Wire diameter: 3.5mm
- Mesh size: 50x100mm
- Frame pipe: 25x25x1.2mm
- Horizontal middle brace: 20x20x1mm
- Feet block: 100x863x7mm
- Feet: 4 prongs
- Finish: hot dipped galvanized and powder coated

Any approved equivalent will be considered.

Question #2: For the provisional ditching, I just put a lump sum for the 90m?

Answer #2: Please provide provisional ditching amounts in per linear meter basis for the cost.

Date: August 13, 2021

Addendum No. 1 Received.

Signature of Bidder

Name of Bidder

Inquiries relating to this ITQ may be directed to:

Anson Hardjojo, Solid Waste and Waste Diversion Coordinator
Regional District of Fraser-Fort George
155 George Street, Prince George, BC V2L 1P8
Phone: 250-960-4400 / Fax: 250-562-8676
Email: anson.hardjojo@rdffg.bc.ca